

**BOQ FOR SUPPLY AND CONSTRUCTION OF FIT-OUT ITEMS OF ATM BOOTH
LOCATED AT GROUND FLOOR OF TRUST BANK PLC. COMPANIGANJ BRANCH
COMPLEX, CHITTA RANJAN AVENUE, COMPANIGANJ, MURADNAGAR, CUMILLA**

ABSTRACT

SL NO	PARTICULARS	AMOUNT (BDT)
A	CIVIL WORKS	
B	PAINTING WORKS	
C	GLASS & PARTITION WORKS	
D	CEILING WORKS	
E	ELECTRICAL WORKS	
F	SIGN BOARD & BRANDING WORKS	
G	MISCELLANEOUS WORKS	
TOTAL AMOUNT=		

IN WORD (TAKA):



BOQ FOR SUPPLY AND CONSTRUCTION OF FIT-OUT ITEMS OF ATM BOOTH LOCATED AT GROUND FLOOR OF TRUST BANK PLC. COMPANIGANJ BRANCH COMPLEX, CHITTA RANJAN AVENUE, COMPANIGANJ, MURADNAGAR, CUMILLA

SI No	Description	Quantity	Unit	Rate	Amount
A. CIVIL WORKS					
01	Dismantling Works:				
	Dismantling of existing all floor tiles, brick wall, pration, electric iteams, plumbing & sanitary, etc. carefully removing this items, including removal the debris to a suitable place outside of site etc. All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.	1	Job		
02	Plastering Works: (For External Wall & Internal surfaces)				
	Minimum 12 mm thick (Internal wall) & minimum 19 mm thick (External wall) cement sand (F.M.1.2) plaster (1:6) with best quality cement to wall both inner and outer surface, finishing the corner and edges including washing of sand cleaning the surface, scaffolding and curing at least for 7 days, including the cost of water, electricity and other charges etc. All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.	50	Sft		
03	Homogeneous Floor Tiles (16" X 16"): (For Internal Floor Area)				
	Supplying, fitting & fixing of (Model: X-Monica-XST 4106 / Equivalent) 16" X 16" Homogeneous mat tiles on floor with 18 mm thick cement mortar (1:2) including cutting and grinding the tile, chipping the surfaces, setting in position keeping horizontal & vertical alignment with care and finish the pointing work including the cost of all materials and tools as require etc. All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.	100	Sft		
				Sub-Total (A)=	
B. PAINTING WORKS					
01	Plastic Paint				
	Painting work with 2 coats of plastic paint/weather coat (Berger) of approved colour and quality over a coat of primer seal including cleaning the surface, rubbing by pumice stone, sand papering, synthetic putty and necessary scaffolding for all floors etc. All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.	300	Sft		
02	Enamel Paint				
	Painting work with 2 coats of enamel paint (Berger) as per approved colour (Green) and quality over a coat of primer seal including cleaning the surface, sand papering, putty and necessary scaffolding for all floors etc. All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.	270	Sft		
				Sub-Total (B)=	



SI No	Description	Quantity	Unit	Rate	Amount
C. GLASS & PARTITION WORKS					
01	Tempered Glass Door : (2'-6"X7'-0")				
	Supplying, fitting & fixing of frameless 10mm thick Tempered glass door with best quality VVP brand (Thailand) all hardwares, SS handle, stoppers, locking arrangement etc. All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.	1	Nos		
02	Fixed Glass Partition:				
	Supplying, fitting & fixing aluminium partition made by Chung Hua brand protector bit OCI silicon, 10mm clear glass with all other hardware etc. All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.	80	Sft		
03	Full Height Wooden Partition & Aluminium Louver Along with Swing Door :				
	Supply, fitting & fixing of Full Height Wooden mid Partition made of MS/Wooden frameing at 2'x2' Grid, Aluminium Louver Along with Swing Door, pasted over 1/2" Plain partex including paint with all other hardware etc. All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority. (Area of one side to be measured for payment)	60	Sft		
04	Wooden Drop Ceiling				
	Supply, fitting & fixing of design wooden drop ceiling suspended from existing R.C.C. slab of the building at the level of 8'-0"/8'-6" (or as per direction) height on, made of 1/2" thick white partex/veneer board over frame work of 2" X 1" best quality seasoned Garjon wood section/aluminium frame and 3 coats of plastic paint over primer coat, putty, racking out joints etc. All complete as per design, direction and satisfaction of Bank Authority.	30	Sft		
				Sub-Total (C)=	
D. CEILING WORKS					
01	Perforated Metal Ceiling:				
	Supplying, fitting & fixing of minimum 0.70 mm thick perforated metal false ceiling hanging with G.I runner over powder coated L angle of section 1"X1" at edges, at 2'-0"X2'-0" grid suspended from ceiling by rowel plug, iron angles, 12 SWG G.I wire, screws, hooks, nails etc. maintaining straight lines and desired finished level at bottom face with vertical or beams by electric drill machine and mending damage if any during execution including the cost of all materials, accessories, scaffolding, labour for installation etc. All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.	60	Sft		



SI No	Description	Quantity	Unit	Rate	Amount
02	ACP Canopy Ceiling & Wall Paneling:				
	Supplying, fitting & fixing of minimum 3 mm thick Aluminium Composite Panels (ACP-Black Matt) false ceiling hanging with design canopy structure work with Best quality 2"x2"/1.5"x1.5" MS angle/MS holo box, royel plug, iron angles, 12 SWG G.I wire, rivit, screws, hooks, nails etc. maintaining straight lines and desired finished level at bottom face with vertical or beams by electric drill machine and mending damage if any. During execution including the cost of all materials, accessories, scaffolding, labour for installation etc. All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.	200	Sft		
Sub-Total (D)=					
E	ELECTRICAL WORKS				
01	PVC Pipe Works:				
	Supply, fitting & fixing of PVC pipe including sattel, GI wire, Groove cutting, plastering and M.K steel box. All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.				
	a. 3/4" dia PVC pipe	100	Rft		
	b. 1" dia PVC pipe	60	Rft		
	c. 3/4" dia flexible pipe	50	Rft		
	d. 1" dia flexible pipe	50	Rft		
	e. 1"-1.5" PVC channel	30	Rft		
	f. MK steel box (size 3" x 3')	12	Nos		
02	Cable Works				
	Supply & installation of PVC sheathed single core Copper Conductor BRB/BBS/Bizli(RFL) Brand including power cable covering PVC pipe . All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.				
	a. 2 x 1.5 rm (7-w) BYA (For light /Fan point) R&B	300	Rft		
	b. 2 x 2.5 rm (BYA) (For ATM Power point) R&B	300	Rft		
	c. 2 x 4.0 rm (7-w) BYA (For AC power line) R&B	100	Rft		
	d. 1 x 2.5 re (BYA) Green (Earthing line)	150	Rft		
	e. 2 x 10rm (7- W) NYY (including earth/road cutting, boring, filling, covered with PVC/Flexible pipe etc. as require to complete the work).	80	Rft		
03	Distribution Board /MCB, MCCB.				
	Supply & installation of Sub-Distribution Board (SDB) which made with GP Sheet with heat paint, incomming option DP MCB/TP MCB, outgoing ways 08 ways, 125 A Brass bar, (ABB, Legrand, SUPER STAR BRAND,Kawamura) Circuit breaker will be ABB/Legrand/Energypac/Kawamura- Japan /Super Star Brand). All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.				
	a. SDB Board.(Size: ± 254mm X 254mm X 89mm) (Brand-HAVLES/Equivalent)	1	Nos		
	b. 63A. SP MCB (Main Circuit breaker, Legrand)	1	Nos		
	c. 20A. SP MCB (Legrand) for AC	2	Nos		
	d. 16A. SP MCB (Legrand) for ATM Machine	2	Nos		
	e. 10 A. SP MCB (Legrand) for light and sign board	3	Nos		



SI No	Description	Quantity	Unit	Rate	Amount
04	LED Panel Light :				
	Supply, fitting & fixing (6" Dia) 18 Watt LED Panel light(Brand: Energypac/Energyplus/SuperStar/Pasha) One or Two light to be connected with UPS through power strip using separate wire & plug so that this light point to be used during failure of electricity. All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.	8	Nos		
05	Led Spot Light (5watt) (Movable Single Imported Adopter Type)				
	Supply, fitting & fixing of imported spot light-3/5 watt (china made) including conceal type shade of approved quality with all other imported accessories etc. All complete as per design, direction and full satisfaction of consulting consultant.	3	Nos		
06	Switch & Socket :				
	Supply and installation of following switch & socket of (Legrand, Energypac brand). All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.				
	a. DP switch for sign board	2	Nos		
	b. 10A. 3 gang switch	3	Nos		
	c. 13A. 3 pin multi socket for for ATM, DVR, Router, Power Point	5	Nos		
	d. 15A. 3 pin socket for AC	2	Nos		
07	Power Strip :				
	Supplying power strip (Philips/ Energypac Brand) consisting 5 points . All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.	1	Nos		
08	Digital Single Phase Meter:				
	Supplying power strip (Philips/Legrand/ Energypac Brand) consisting 8 points . All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.	1	Nos		
09	Earthing works :				
	Boring work for earthing: Depth - ±150 ft to 200 ft, Copper Wire - 04 SWG copper wire. Boaring dia - 1.0" dia boring with G.I pipe (Basundhara Gold), screw, nut, bolts and other related goods etc. Cable- connection by 1x4 Rm BYA Green Cable (BRB/BBS/RR/Partex) from Boaring to UPS power Point. Earthing Resistance Value: < 1 OHM and Earthing Leakage Voltage : < 3 V Warrenty- 2 (Two) Years All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.	1	Job.		
				Sub-Total (E)=	

Sub-Total (E)=



SI No	Description	Quantity	Unit	Rate	Amount
F.	SIGN BOARD & BRANDING WORKS				
01	Panaflex Sign Board (±10'-0"x2'-6") Long :				
	Supplying fitting & fixing Panaflex sign board (2'-6"width) including aluminium profile light box, panaflex with UV digital print, Rupban Sheet, electric light set up 4' LED tube ligh (48 Watt- super star/tachi/pasha),starter, GI wire , Electric power cable for connection cable use - 40x76 flexible FRLS cable (BRB/BBS/RR/Bizli), 1.5rm Electric FRLS cable for main connection, GI wire, 12x12 mm square MS box, MS angle with 02 coat of emamel paint & other equipments etc. All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.(Area of one side to be measured for payment)	22	Sft		
02	Panaflex Both Side Sign Board (3'-0"x4'-0"x2) :				
	Supplying fitting & fixing panaflex both side sign board including aluminium profile light box, panaflex with UV digital print, Rupban Sheet, electric light set up 4' LED tube ligh (48 Watt- super star/tachi/pasha),starter, GI wire , Electric power cable for connection cable use - 40x76 flexible FRLS cable (BRB/BBS/RR/Bizli), 1.5rm Electric FRLS cable for main connection, GI wire, 12x12 mm square MS box, MS angle with 02 coat of emamel paint & other equipments etc. All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.(Area of one side to be measured for payment)	24	Sft		
03	Inject print				
	Supply, fitting & fixing graphics of approved design over glass door and partition (Inside/outside pasting) etc. All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.	100	Sft		
04	Branding Works				
	Supply, fitting & fixing of 5mm thick PVC board with Bank Branding. All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.	120	Sft		
05	Push Pull Sticker:				
	Supply, fitting & fixing graphics of approved design over glass door and partition (Inside/outside pasting) etc. All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.	2	Nos		
06	NOTICE BOARD:				
	Supply, fitting and fixing of notice board made of 8mm clear glass (12"x18") with digital Print with SS Knob. All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.	3	Nos		
Sub-Total (F)=					



SI No	Description	Quantity	Unit	Rate	Amount
G.	MISCELLANEOUS WORKS				
01	Guard Tool :				
	Supplying a guard tool plastic body RFL/Partex/Bengal as approved by the Bank authority. All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.	1	No		
02	Pedal Bin (Waste Paper Box)				
	Supply, fitting & fixing of RFL Pedal Bin (15-18L)) made of high quality Gray colored. All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.	1	No		
03	Check Writing Desk:				
	Supply, fitting and fixing of check writing desk made of 10mm clear glass with SS L Clamp. All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.	1	Nos		
04	DVR Rack ±(1'-6"x1'-6"x2"-0")				
	Supply, fitting & fixing of DVR rack made of laminated board (18mm thick) of approved color and quality including hardwares & etc. All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.	1	Nos		
05	Plastic Water Jar for AC Drain Line Water Disposal				
	Supply, fitting & fixing of plastic water jar, Capacity: 20 Ltr. All completing as per direction of the Engineer- in-charge & full satisfaction of the Bank Authority.	2	No		
Sub-Total (G)=					

